

- Spectrum coaxial installation update- the new coaxial cables in the condo units in the 5 and 7 stacks have been installed and tested. The individual condo coaxial cables for each of those units was placed in the existing metal conduit. Therefore, each unit will have its own protected line. This was a test run and we are very pleased with the outcome.
- The plan is to replicate the same procedure in the remaining 16 stacks. Starting October 23rd or 24th, they will be precutting the sheetrock near the baseboard in each unit on the first floor units so that the installation crew can place the coaxial cable behind the sheetrock rather than leaving it exposed in the unit as it is currently. This access opening will be a few inches above the baseboard and be about four inches wide and run from the wall to the cable outlet box. Once the coaxial cables have been installed and tested, the condominium will have the access sheetrock that was removed reinstalled and prepared for painting. Once the drywall has been repaired, we will repaint it if you provide us with your paint so that we have a perfect match. All of the condo units in the stack will be impacted during this installation and testing process of that stack.
- Once a plan for the installation has been finalized, the manager will notify the owners of the schedule. Since the coaxial cables will be feed into the metal conduit on the first floor a substantial amount of the work will be at that location. However, every unit will be affected by this important installation project. Once it is completed every condo unit will have its own coaxial cable feeding the telephones, televisions, internet, etc. This should increase the bandwidth available to our family and guests. Thanks for your cooperation.